BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT28874

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/04/2017-18, Date: 24.07.2017

Package No. 03 Package consists of 21 works

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
1	7483.705	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, roads drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up lift 1.5, excavated surface leveled and neatly dressed disposed earth to be leveled after breaking of clods and neatly dressed as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	178.07	Rupees One Hundred Seventy Eight and Seven Paise Only
2	13.2	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .(Road)	Cum	5520.15	Rupees Five Thousand Five Hundred Twenty and Fifteen Paise Only
3	2129.05	Removing B.S.slab of Drain and stacking as per the directions of the Engineer-in-charge of the work .	Sqm	70.32	Rupees Seventy and Thirty Two Paise Only
4	7079.297	Removing and refixing stone slabs of drains and pointing in CM (1:3) as per the directions of the Engineer-in-charge of the work .	Sqm	86.20	Rupees Eighty Six and Twenty Paise Only
5	1375.589	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per the directions of the Engineer-in-charge of the work .	Sqm	712.28	Rupees Seven Hundred Twelve and Twenty Eight Paise Only
6	2251.184	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per the directions of the Engineer-in-charge of the work .(Road)	Sqm	883.54	Rupees Eight Hundred Eighty Three and Fifty Four Paise Only
7	8276.797	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	93.00	Rupees Ninety Three Only
8	1648.425	Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	52.17	Rupees Fifty Two and Seventeen Paise Only
9	17722.13	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms as per the directions of the Engineer-in-charge of the work .	Cum	124.12	Rupees One Hundred Twenty Four and Twelve Paise Only
10	600.6	Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	342.53	Rupees Three Hundred Forty Two and Fifty Three Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the contractor

DIRECTOR

Executive Engineer

o.	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
11	1802.354	Providing,laying, spreading and compacting crushed stone aggregates of granite/trap/ basalt to wet mix macadam specification including pre mixing the Material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density. complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	1891.85	Rupees One Thousand Eight Hundred Ninety One and Eighty Five Paise Only
12	6635.9	Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	32.89	Rupees Thirty Two and Eighty Nine Paise Only
13	5212.24	Cleaning the existing WBM Road surface including removing of binding materials and other foreign matter with wire brushes and small picks sweeping with brooms or soft brushes and finally dusting with old gunny bags and bar or compressed air to receive bituminous treatment including cost of all materials, labhour, HOM of machineries complet as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	14.74	Rupees Fourteen and Seventy Four Paise Only
14	11127.74	Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kglsqm using mechanical means complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	29.49	Rupees Twenty Nine and Forty Nine Paise Only
15	273.6426	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixd material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	6131.49	Rupees Six Thousand One Hundred Thirty One and Forty Nine Paise Only
16	210.775	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen as per the directions of the Engineer-in-charge of the work .	Cum	7618.42	Rupees Seven Thousand Six Hundred Eighteen and Forty Two Paise Only
17	104726.9	Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	3.40	Rupees Three and Forty Paise Only
18	114857.9	Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	13.61	Rupees Thirteen and Sixty One Paise Only
19	4743.08	Providing and laying bituminous concrete 30-40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 5.4% of mix and filler, transporting the hot mix to work site, laying with a mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction complete in all respects as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	8686.84	Rupees Eight Thousand Six Hundred Eighty Six and Eighty Four Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the contractor

DIRECTOR

22/10

Executive Engineer

22/10

No.	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
20	4320.791	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	580.71	Rupees Five Hundred Eighty and Seventy One Paise Only
21	313.2	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	885.81	Rupees Eight Hundred Eighty Five and Eighty One Paise Only
22	313.2	Construction of dry lean cement concrete mix CC1:5:10 with OPC cement @160Kgs, with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum Sub- base over a prepared sub-grade with (coarse and fine aggregate conforming to IS: 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, cement content not to be less than 160 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	4265.73	Rupees Four Thousand Two Hundred Sixty Five and Seventy Three Paise Only
23	905.27	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	6653.22	Rupees Six Thousand Six Hundred Fifty Three and Twenty Two Paise Only
24	92.8	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Conrete Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms and 2Ltr of Primer per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	733.83	Rupees Seven Hundred Thirty Three and Eighty Three Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the contractor

DIRECTOR

22/10

Executive Engineer

22/10

	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
25	88	LED Street light.Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminare > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with ..... W System Power consumption. LED Efficiency>130lm/w at 1W & FixtureEfficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part.	no	20030.40	Rupees Twenty Thousand Thirty and Forty Paise Only
26	135	Supplying and Fixing of..... mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires. Using 32mm dia G.I.pipe as per the directions of the Engineer-in-charge of the work .	no	955.51	Rupees Nine Hundred Fifty Five and Fifty One Paise Only
27	440	Wiring for lighting/power circuit using one of PVC insulated 1100v grade stranded Aluminium unsheathed wire single core/multi core cable in open or consealed system of wiring. a)4 sqmm. as per the directions of the Engineer-in-charge of the work .	no	8.03	Rupees Eight and Three Paise Only
28	150	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of ROUP-A.3.5 core 25sqmm as per the directions of the Engineer-in-charge of the work .	rmt	177.19	Rupees One Hundred Seventy Seven and Nineteen Paise Only
29	150	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct.25 sqmm to 75 sqmm as per the directions of the Engineer-in-charge of the work .	rmt	37.24	Rupees Thirty Seven and Twenty Four Paise Only
30	55	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes25 sqmm Long Barrel as per the directions of the Engineer-in-charge of the work .	no	22.03	Rupees Twenty Two and Three Paise Only
31	426.135	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20.as per the directions of the Engineer-in-charge of the work .	Cum	549.11	Rupees Five Hundred Forty Nine and Eleven Paise Only
32	1184.764	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	5723.17	Rupees Five Thousand Seven Hundred Twenty Three and Seventeen Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the contractor

DIRECTOR

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
	1197.248	Providing laying plain/ reinforced cement concrete M20 Grade for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc. complete as per approved drawing and design as per the directions of the Engineer-in-charge of the work .	Cum	11804.75	Rupees Eleven Thousand Eight Hundred Four and Seventy Five Paise Only
34	63.03	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work .	t	68740.46	Rupees Sixty Eight Thousand Seven Hundred Forty and Forty Six Paise Only
35	5556.35	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift as per the directions of the Engineer-in-charge of the work .	Sqm	102.08	Rupees One Hundred Two and Eight Paise Only
36	382.5802	Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	4748.90	Rupees Four Thousand Seven Hundred Forty Eight and Ninety Paise Only
37	108.567	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	5676.67	Rupees Five Thousand Six Hundred Seventy Six and Sixty Seven Paise Only
38	773.59	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	110.02	Rupees One Hundred Ten and Two Paise Only
39	80.2685	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.530 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	6171.18	Rupees Six Thousand One Hundred Seventy One and Eighteen Paise Only
40	420	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	1034.39	Rupees One Thousand Thirty Four and Thirty Nine Paise Only
41	3091	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as per the directions of the Engineer-in-charge of the work .	no	355.00	Rupees Three Hundred Fifty Five Only
42	486.85	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications	Sqm	68.05	Rupees Sixty Eight and Five Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the contractor

DIRECTOR

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
43	440	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) as per the directions of the Engineer-in-charge of the work .	rmt	928.91	Rupees Nine Hundred Twenty Eight and Ninety One Paise Only
44	957	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint as per the directions of the Engineer-in-charge of the work .	Sqm	747.44	Rupees Seven Hundred Forty Seven and Forty Four Paise Only
45	469	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint as per the directions of the Engineer-in-charge of the work .	rmt	367.48	Rupees Three Hundred Sixty Seven and Forty Eight Paise Only
46	20	Fabricating, providing and erecting in poiston of Hot dip galvanised M S Ornamental security Grill using 75 x 12mm M S Flat for alround frame work with verticals at the centre and horizontal centere support M S Square of 20 x20 mm of different heights as shown in the drawing are to be fixed at 16 cms C/C for suqare bars of full height and at 8cms C / C for bottom rods providg ornamental C I Designers at the botom and C I arrows inthe midle and top. The entire frame work is to be fixed by means of expansion bolts to the brick pillars with necesary drillling holes. the work includes providng two coats of enamel painting over one coatr of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes with all lead and lift, loading, transporting and unloading using hoist pulley cranes, scaffolding charges and all other incidental charges required for successful completion fo the work as per specification and drawings as per the directions of the Engineer-in-charge of the work .	kg	9784.23	Rupees Nine Thousand Seven Hundred Eighty Four and Twenty Three Paise Only
47	626.52	Removing and resetting of footpath slab as per the directions of the Engineer-in-charge of the work .	Sqm	141.78	Rupees One Hundred Forty One and Seventy Eight Paise Only
48	27.36	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry.B. Rubble stone masonry in cement mortar as per the directions of the Engineer-in-charge of the work .	Sqm	401.67	Rupees Four Hundred One and Sixty Seven Paise Only
49	41.04	Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications (available stones) as per the directions of the Engineer-in-charge of the work .	Cum	2979.54	Rupees Two Thousand Nine Hundred Seventy Nine and Fifty Four Paise Only
50	29.974	Furnishing and Placing Reinforced/ Prestressed cement concrete in super-structure as per drawing and Technical Specification complete as per specifications. D. RCC / PSC with OPC cement design mix M35 @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @0.68cum and fine aggregates @ 0.45cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, Case - II : Using Batching Plant, Transit Mixer & Concrete Pump as per the directions of the Engineer-in-charge of the work .	Cum	7899.70	Rupees Seven Thousand Eight Hundred Ninety Nine and Seventy Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the contractor

DIRECTOR

Executive Engine

22/10

	Approved Qty.	Description	Unit	Approved Tender Rates of C G CHANDRAPPA	
				In Figures	In Words
	4.05	Supplying , fitting and placingTMT bar Fe 550 reinforcement in sub-structure complete as per drawing & technical specification complete as per the specification as per the directions of the Engineer-in-charge of the work .	t	71909.41	Rupees Seventy One Thousand Nine Hundred Nine and Forty One Paise Only
52	254.1	Construction of granular sub-base by providing close graded crushed stone aggregates of granite / trap / basalt material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method as per the directions of the Engineer-in-charge of the work .	Cum	1781.83	Rupees One Thousand Seven Hundred Eighty One and Eighty Three Paise Only

For CGC INFRA PROJECTS PVT LTD

Signature of the Contractor

DIRECTOR

Executive Engineer

Byarayanapura Division

BBMP, Bangalore - 92

22/10

22/10